



# Critical Risks

Transport		Any work-related driving activities and the safe operation of Coates transport vehicles, including contractors for the purpose of performing work. Includes Load Restraint, Towing, Load & Unload	
Working with or around high-risk plant		Any work activity performed near or using high-risk plant including cranes (mobile, truck mounted, gantry), excavators, elevated work platforms (boom, scissor, knuckle), forklifts and other plant determined as 'high risk' following a risk assessment.	
Working at heights		Any work where there is a risk of falling from one level to another. Additional controls are required for high-risk construction work 2m or more.	
Electrical hazards		Any work where the risk of an electrical hazard may be present. Includes the use of electrical equipment as well as working on or near electrical hazards.	
Working in or near traffic		Work activity where vehicles, plant and pedestrians interact whilst travelling on a public or private roadway, or within construction sites or branches.	
Temporary works		Temporary works are used to support or protect an existing structure or the permanent works during construction, support an item of plant or equipment, maintenance work on existing facility, support an excavation or to provide access.	
Stored energy		The risks associated with potential release of energy during servicing, commissioning, repairing or modification works on plant and equipment.	
Crane lifting		Mechanical means utilised to lift components. This includes mobile cranes, gantry cranes, vehicle loading cranes and forklifts.	
Remote or lone worker		Remote or isolated work is where a worker may be required to work or travel and be isolated from other personnel.	
Working above or near water		This includes working within 3m of a body of water where there is no edge protection, working on any inclined surface adjacent to a body of water and working on temporary or permanent structures above or near water (gangways, pontoons and bridges).	